G. R. S. 58]

Previous references.

File No. 30f. 96

Serial Nos. 25-26.

1901.

(Municipal)

Later references.

GENERAL AND REVENUE SECRETARIAT.

Serial Nos. 25- 26

Paper **Part B for**

SUBJECT.

Loan to Nanjangud municipality for water and Road work. (Nilattabhinay

Sl. 25. From The Presidt Mysore no 156. D. 17 8

Requests to obtain sanction for half o the Cost of the estimate for laying out additior line of pipes at Nanjangud.

Sl 26 To The Presidt Mysore. To Comptr. To Cf En

No. 3677-79 Dated 2-9-01

GPB—3,500—21-7-14

Sanctions the above stating that Cost should be debited to Provincial. Fin

Note

Letter no. 156 dated the 17th August 1907 from the President of the Municipalities in the Mysore District

---

The President submits with the above letter Mr. Lee's report showing the necessity for laying an additional pipe line of 12" diameter to feed the service reservoir at Ranjangude and solicits sanction to a sum of Rs 44,82½. The moiety of the cost being met from State Funds.

Half the entire cost of the Ranjangude water-supply project viz Rs 38,604/- was met

Water Supply - 27,948
Opening out roads - 4656
Storage reservoir - 6000
38,604

met from State Funds, and
the other half was ~~considered~~ treated
as a loan to the Municipality

The President states that
the Board have agreed to
bear half the cost.

The estimated closing balance
of the Ranyanyude Municipality
for the current year is Rs 1294/7
which is less than the minimum
balance by Rs 414. If a moiety
~~Contribution forwarded~~.
of the cost payable from
municipal funds be
sanctioned, the balance
will further be reduced
to the extent of Rs 441½
May this however be
approved.

Receipts) 6830
1708
1294
414

Sd D. Muthuraja

Orders regarding
the other moiety being
paid from Provincial
funds have to be issued
from the D P W

Submitted for orders
of the 3rd Councillor, Dy 24/8/01

24/8/01

133

SECTION Grant

FILE No. 2449 21-8-01

SERIAL No. 1

1901-1902,

L 265

From

H. Ramanujaiengar Esquire,
President, Local Fund Boards,
Mysore district.

To

H. V. Nanjundiah, Esquire,
Secretary to the Government of Mysore
Revenue and General Department

Dated 17th [illegible]

Despatched

Received

General No. 156

No.

Enclosure No. Nil

Requesting him to obtain the sanction of Government for half of the estimated cost of Rs 883 for laying an additional line of pipes to water-supply Reservoir at Nanjangud to be met from Provincial Funds.

A Sd note file
Engr 21/8/01

Recd 22/8

Note put up
Read
24/8

OFFICE OF THE PRESIDENT,
LOCAL FUND BOARDS, MYSOR

Enclosure One + 1 = 2
No. 156
Dated 17th August 1901.

From H. Ramanujaiengar Esquire,
~~The~~ President,
Local Fund Boards.
Mysore District.

To H. V. Nanjundiah Esquire,
~~The~~ Secretary to the Government of Mysore,
Revenue and General Departments.

SIR,

I have the honor to state that the Superintending Engineer of the Sanitary works sent in an estimate amounting to Rs 883 for laying an additional line of pipes to the water-supply Reservoir at Vanjangud, as the present feeding-pipe of 7" diameter is not able to fill the reservoir for the reasons stated in the enclosed report. The matter was discussed by the Municipal Board, which has agreed to bear half the cost of the estimate. I request you to be so good as to obtain the sanction of Government for the other half of the estimated cost being met out of the Provincial Funds, and the work being put in hand.

of Superintending Engineers No. 757
of the 18th August 1901 on the subject is
herewith submitted for reference.

I have the honor to be,
Sir,
Your most obedient Servant,
K Ramalingam Iyer
Offg President
Mysore District

From

The Chief Engineer
of Mysore

To.

The Superintending Engineer
Sanitary works.

Dated Bangalore 31st January 1901.

General No 4210

Superintending Engineer's No 1767/378 dated 24th instant, stating that the Municipal Board of Ranjangud had agreed to bear half the cost of the estimate for laying the additional line of pipes to the Service Reservoir of that town; and enquiring whether the work may be put in hand

"

In reply, have the honor to inform the Superintending Engineer that the being a municipal work (vide para 2 of his No 532/122 dated 15th February 1901) the officiating Chief Engr

province to at
tached in hand, on the terms
as regards funds, proposed in
Municipal President's No.
27 dated 19th instant.

2. As suggested in this
Office No. 1176 dated 28th Jan
uary 1901, the Municipal
President should be asked
to address Government in the
General Department by whom
Municipal Funds are adminis
-tered.

(Signed) W. Dalton
Asst. Secretary
Office of Chief Engineer
Mysore.

1824
757

Dated Bangalore 1-8-01

The President of Municipalities
Mysore

I have the honor to forward herewith copy of the above for information with reference to his No. 27 of 19-7-1901 and to request favor of action on the suggestion made in para two the above -

Sd. Ranganath Lee.
Superintending Engineer
Sanitary Works.

"Copy"

17.8.01 for Officiating President
Sd/ B. Muthu Rao

28

Report to accompany the Estimate of the probable cost of laying an additional line of pipes to feed the Service Reservoir at Nanyang-Gate.

The present feeding pipe to the Reservoir at nanyangwe is of 7" diameter, and is not able to fill the Reservoir After the Reservoir fills to 3 feet, the rate of discharge of the 7" pipe is about equal to the loss from percolation from the Reservoir and the Reservoir has therefore never more than 3 feet water. Also, it takes nearly 7 days for the Reservoir to fill 3 feet deep and as during the hot season the channel from which it is filled is not kept open for more than 10 days in a month, the Reservoir does not last for the town supply for the remaining 20 days.

II To enable

and t dep i.e. 4½ feet is proposed to lay an additional pipe line of 12" in diameter to the Reservoir. The greatest pressure being only 5 feet the cracked iron pipes in Stock of the Mysore Water Supply and the surplus cement pipes of the Sewerage of the South East portion of Mysore are proposed to be used at reduced prices.

III To prevent the water running back into the Hulhalli Channel when it is run dry, a 12" valve is proposed at the inlet of the pipe line, which is expensive for such a short line but no cheaper contrivance will work satisfactorily.

/Signed/ Standesh Lee

Copy

/Signed/ Standesh Lee

Superintending Engineer

Sanitary works

9

"Copy"

Mr Mackie

for offg President
Municipalities
Mupore District

Dated 19th August 1901 } 2 ys

SECTION Public

FILE No. 561/04

Read.

Letter no 156 dated the 17th August 1907 from the President of the Municipalities in the Mysore District, submitting Mr. Lee's report showing the necessity for laying an additional pipe line of 12" diameter to feed the service reservoir at Ramanagaram, and soliciting sanction to a moiety of the estimated cost of Rs 883/- being met from Provincial funds, the Municipal Board of Ramanagaram having agreed to bear the other moiety of the cost.

Order thereon

Govt are pleased to authorize the work being put in hand half the cost thereof viz Rs 441½ being met out of the savings

No 3677-79 9/9/07.
L.7176-94

Ch: and Sch: Engineer.

of the Champaigude Municipality for the current official year.

2, Orders will be passed by Govt in the P.W.D regarding ~~the adjustment of~~ the other moiety of the cost, proposed to be debited to Provincial funds.

30/8/01

For Secty.
GK
30.8.01

To
The Presdt of the Municipal Improvement Committee.
Chief Engineer & Secty to Govt
with Copy of the letter & of its Enclosure.

Memo

Copy forwarded to the Secty P.W.D for needful being with Copy of the letter read above & its enclosure.

By order

For Secty.
GK
30.8.01

GK 31/8/01